

ACCEPTED BY THE HILLSDALE CO. SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 342 OF 1960 AT A MEETING HELD ON 10/30/97 AT AL RINGENBERG CO. REP.

LIBER 3 PAGE 231
REMONUMENTATION

128732 RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

For corners in

HILLSDALE
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6S</u> R <u>1W</u>	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Judy VanZandt
SURVEY &
REMONUMENTATION

FEB 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Jeffrey A. Bieszka, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824) County Survey (Otis Briggs 1839)
Corner was a 10" Beech Tree Section corner (?)

LCRC (Bruce Leone L 573 P 155)
Set Harrison Monument
8" Maple N 80 W 163.37 ft. 8" Maple S 24 W 101.48 ft.
8" Cedar S 59 E 95.01 ft. 10" Maple S 57 W 78.54 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Bruce Leone dug and found a 11" pointed stone with 12" stone skinning tool, two smaller stones and shaft of decayed wooden post. Said stone being 19" below surface of existing N-S asphalt roadway. He found a very large spike 8.3 feet South and 2.5 feet East of said stone. He lowered said stone and set a Harrison monument. I found said Harrison monument as witnessed by Leone. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail w/tag 12" Maple S 25 W 101.50 ft.
Stop sign post N 88 E 46.20 ft.
center Phone Box S 37 E 67.08 ft.
center Phone Box S 30 W 62.29 ft.



Signed by [Signature] Date 25 November 1997
Surveyor's Michigan License No. 41093