



LIBER 3 PAGE 232  
REMONUMENTATION

128733 RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

*Judy VanZandt*  
REC. OF DEEDS

SURVEY &  
REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number  
SECTION

For corners in

HILLSDALE  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>6S</u> R <u>1W</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Jeffrey A. Bieszk, in a field survey on 12 November, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO set by Robert Clark Jr. (1824)  
6" Elm S 68 W 21 lks  
4" Elm S 28.5 E 14 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron with ribbon and a chisel like end. Iron was in the centerline of Waldron Road, no occupation East or West. Dug under iron and found nothing. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box  
Nail w/tag R.R. fence post N 87 E 23.42 ft.  
Nail w/tag 60" Maple N 27 E 58.43 ft.  
Nail w/tag Twin Maple S 55 E 29.23 ft.  
Nail w/tag Power Pole S 35 W 58.08 ft.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by *[Signature]*

Date 25 November 1997

Surveyor's Michigan License No. 41093