

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-30-97
AL RINGENBERG, CO. REP.

LIBER 3 PAGE 233
REMONUMENTATION

128734

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'97 NOV 26 PM 4 08

For corners in

HILLSDALE
(County)

Located In: Corner Code #

- | | | |
|---------------------------------------|-------------------------|-------------|
| 1. Public Land Survey | T <u>6S</u> R <u>1W</u> | <u>G-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Judy VanZandt
REC. OF DEEDS
SURVEY &
REMONUMENTATION
FEB 11 1998
Register of Deeds Stamp & File Number
SECTION

Jeffrey A. Bieszk, in a field survey on 12 November, 19 97,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO set by Robert Clark Jr. (1824)
- 6" Beech N 26 E 18 lks
- 12" Beech West 9 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rebar 13.79 feet West of found iron at G-1 Township 7 South, Range 1 West, GLO falling 13.86 feet and centerline of Culbert Road. Dug under iron found nothing else, there was no other information for this corner. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Nail w/tag 8" Maple N 60 W 49.66 ft.
- Stop Sign post N 82 E 64.71 ft.
- Nail w/tag Power Pole N 05 W 81.92 ft.
- center Phone Box S 45 W 39.58 ft.



Signed by *[Signature]* Date 25 November 1997
Surveyor's Michigan License No. 41093