

127899

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 211

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/19/97 AT AL RINGENBERG, CO. REP.

HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 NOV 3 PM 4 19

Janey VanZandt
REC. OF DEEDS

For corners in

<u>HILLSDALE</u>	Located in:	Corner
Code #		
(County)		
WHEATLAND TWP.		
1. Public Land Survey	<u>T 6 S R 1 W</u>	<u>K-5</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

SURVEY & REMONUMENTATION

FEB 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, EDWARD W. REED, in a field survey on OCTOBER 6, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 11-12-13-14

NO INFORMATION AVAILABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON WITH FLAGGING, FOUND NOTHING BELOW

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NAIL & WASHER CORNER WOOD ANCHOR POST, S38E 45.33'
NE CORNER TEL. PED, S48W 45.47'
NAIL & WASHER E. SIDE POWER POLE, S35W 53.41'
SW CORNER TEL. PED, N51W 50.9'
NAIL & WASHER N SIDE 36" MAPLE, S75W 116.47'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

Date OCTOBER 6, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985