

'94 NOV 28 AM 11 07

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 11-28-94 AL RINGENBERG, CO. REF.

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Judy VanZandt*  
REG. OF DEEDS

For corners in  
Hillsdale  
(County)

Located in: Corner Code #

- |                                       |   |       |    |       |
|---------------------------------------|---|-------|----|-------|
|                                       |   | 6S    | 2W | C-13  |
| 1. Public Land Survey                 | T | _____ | R  | _____ |
|                                       | T | _____ | R  | _____ |
|                                       | T | _____ | R  | _____ |
|                                       | T | _____ | R  | _____ |
| 2. Property Controlling in Section    | S | _____ | T  | _____ |
|                                       | S | _____ | T  | _____ |
| 3. Miscellaneous Property in Sec.     | S | _____ | T  | _____ |
|                                       | S | _____ | T  | _____ |
| 4. Lot No. _____, Recorded Plat _____ |   |       |    |       |
| 5. Private Claims _____               |   |       |    |       |

SURVEY &  
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

Frederick J. Cutcher November 18 19 94

I, \_\_\_\_\_, in a field survey on \_\_\_\_\_, 19 \_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Survey #1207, Nov. 3, 1897, George Mark, Co. Surveyor: Stone, East 91 links.

Robert E. Burris, Sr., LCRC Liber 1, Page 483, June 5, 1975: Found stone for corner C-1, T7S, R2W. Set R.R. spike 91links (60.06') West. GLO = 91 links West of C-1, T7S, R2W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike below pavement, 60.60' West of C-1 (N.E. corner Sec. 6, T7S, R2W) in centerline of East/West road; 4'± West of centerline of road to North. Dug down 24"±, nothing else found at this spot. Set 3/4"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monument box  
In centerline E/W road; 4'± W. of centerline of road to North  
Top center telephone stanchion N. 40° W., 44.46'  
Top center telephone stanchion N. 32° E., 60.40'  
Top center telephone stanchion S. 62° E., 66.16'  
Nail in S.E. side 24" Hickory N. 29° E., 66.30'



Signed by *Frederick J. Cutcher*

Date November 23, 1994

Surveyor's Michigan License No. 24592