

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 MEETING HELD ON 11-29-94 AL RINGENBERG, CO. REP.

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 07

Judy VanZandt REG. OF DEEDS

For corners in Hillsdale (County)

Located In: Corner Code #

- 1. Public Land Survey T 6S R 2W
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

D-13

SURVEY & REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

- 4. Lot No. Recorded Plat
5. Private Claims

Frederick J. Cutcher November 17, 1994

I, Frederick J. Cutcher, in a field survey on November 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column C and row 13.

A. Description of original monument and accessories and/or subsequent restoration: Survey #945, Apr. 9, 1883, George Mark, Co. Surveyor: Stake and stone; Hickory 5' N. 9 1/2° E., 38 1/2 links; W. Oak 9' N. 47 1/4° E., 59 1/2 links. Records of A.E. Ringenberg: M. Vernier, Apr. 11, 1975: Set road commission monument; P.K. nail E. side 20" Maple, N. 30° W., 24.95'; P.K. nail N.E. side 16" Maple, S. 60° E., 47.49'; P.K. Nail W. side 4" Maple, S. 05° E., 25.78'. Keyno Shellenberger, LCRC Liber 646, Page 100, Dec. 27, 1991: Found Harrison monument. GLO proration = 74.58' West of D-1, T7S, R2W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found Harrison marker on North edge of gravel road, 2' West of fence to the North and 74.84' West of D-1, T7S, R2W. Replaced with 3/4"x36" County remonumentation rod and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 3/4"x36" County remonumentation bar on N. edge of road, 2' W. of fence to N. 74.84' West of D-1 T7S, R2W S.W. corner mailbox post N. 15° E., 2.54' Nail & tag #30101 E. side R.R. tie anchor post, North 20.92' Nail in S.W. side 18" Ash, S. 50° E., 47.32' Top center corrugated metal pipe driveway culvert N. 80° W., 21.27'



Signed by Frederick J. Cutcher Surveyor's Michigan License No. 24592

Date November 23, 1994