

007939

RECORDED  
HILLSDALE CO. MICH.

'98 AUG 7 AM 10 10

LIBER 3 PAGE 252

HILLSDALE COUNTY REMONUMATION CORNER  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970



For corners in

HILLSDALE COUNTY  
ADAMS TOWNSHIP

Located In: Corner Code #

1. Public Land Survey T 6 S R 2 W E-7  
T R  
T R  
T R  
2. Property Controlling S T R SURVEY & REMONUMENTATION  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R FEB 23 1999

Judy VanZandt  
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat SECTION  
5. Private Claims \_\_\_\_\_

I, EDWARD W. REED, in a field survey on JUNE 26, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 16, 17, 20, 21,

A. Description of original monument and accessories and/or subsequent restoration:

- 1825: ROBERT CLARK, JR., DEPT SURVEYOR, CORNER SET
- 1868: GEO. A. MARK, COUNTY SURVEYOR - SURVEY # 476, TWO STONES IN MUD
- 1980: ALAN RINGENBURG, SURVEYOR - FOUND BOLT, RESET WITH 1/2" IRON BAR, RECORDED IN LCRC LIBER 2, PAGE 16
- 1987: BRUCE LEONE, SURVEYOR - FOUND TWO POINTED STONES SIDE BY SIDE WITH BROKEN CROCKERY AND DECAYED WOOD 18" BELOW SURFACE OF ROAD, SET 4" HARRISON MARKER, RECORDED IN LCRC LIBER 573, PAGE 133

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND HARRISON MARKER AS DESCRIBED BY LEONE IN LIBER 573, PAGE 133

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH PAVED ROAD

PK NAIL 18" UP NW SIDE OF 8" OAK N 16 E 27.37'  
PK NAIL 18" UP N.W. SIDE OF 18" ASH N 78 E 63.78'  
PK NAIL 12" UP N.E. SIDE OF NORTHERLY 8" TWIN HICKORY N 46 E 48.50'  
PK NAIL 17" UP N.E. SIDE OF 4" OAK S 11 E 32.20'  
CENTER OF 12" BOX ELDER S 45 W 44.4'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by Edward W. Reed

EDWARD W. REED

Date AUGUST 5, 1998

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

