

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 11-28-94 AL RINGENBERG, CO. REF

LIBER 3 PAGE 40

97381

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'94 NOV 28 AM 11 07

*Judy VanZandt*  
REG. OF DEEDS

For corners in

Hillsdale  
(County)

Located In:

Corner Code #

- |                                    |                         |             |
|------------------------------------|-------------------------|-------------|
| 1. Public Land Survey              | T <u>6S</u> R <u>2W</u> | <u>E-13</u> |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
|                                    | T _____ R _____         | _____       |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____       |
|                                    | S _____ T _____ R _____ | _____       |

SURVEY &  
REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number  
COMMISSION

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Frederick J. Cutcher, in a field survey on November 17, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey #934, Oct. 5, 1882, George Mark, Co. Surveyor: Stone (no witnesses)

Robert E. Burris, Sr., LCRC Liber 1, Page 485, June 9, 1975: Found stone for N.E. corner of Sec. 5, T7S, R2W and set corner 89.10' West.

GLO = 135 links West of E-1, T7S, R2W

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 60D spike over Harrison marker and brick, 89.1' West of E-1, T7S, R2W. Replaced with 3/4"x36" County remonumentation rod and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar  
89.1' West of E-1, T7S, R2W

Top center telephone stanchion, N. 25° W., 45.33'

N.E. corner barn, S. 65° W., 62.78'

Nail in W. side 12" Pine, S. 5° E., 80.40'

Bottom N.W. corner concrete post, East 113.15'



Signed by Frederick J. Cutcher

Date November 23, 1994

Surveyor's Michigan License No. 24592