

007940

RECORDED
HILLSDALE CO. MICH.



HILLSDALE COUNTY REMONUMATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 AUG 7 AM 10 10

Judy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE COUNTY
ADAMS TWP.

Located In: Corner Code

- 1. Public Land Survey T 6 S R 2 W G-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling in Section S _____ T _____ R _____
S _____
T _____ R _____
- 3. Miscellaneous S _____
T _____ R _____
- Property in Sec. S _____
T _____ R _____

SURVEY &
REMONUMENTATION

Register of Deeds Stamp & File Number

FEB 23 1999

SECTION

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 26, 19 98
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 15-16-21-22

A. Description of original monument and accessories and/or subsequent restoration:

1973: ROBERT BURRIS, SR., SURVEYOR- FOUND IRON PIPE, SET 1" IRON OVER EXISTING IRON, RECORDED IN LCRC LIBER 1, PAGE 301

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON ROD INSIDE OF 1" X 4' LONG PIPE, NO OTHER EVIDENCE FOUND.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED IRON PIPE, SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX, 4" BELOW GRAVEL ROAD SURFACE.

- PK NAIL W. SIDE OF 24" BLACK LOCUST, NORTH 31.82'
- PK NAIL SE SIDE POWER POLE, S 50 W 42.73'
- WEST END ROAD CULVERT, N 40 W 27.7'
- EAST END ROAD CULVERT, N 15 E 20.6'
- SW CORNER HOUSE N 40 W 153.2'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed
EDWARD W. REED

Date AUGUST 5, 1998

Surveyor's Michigan License No. 33985

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

