

007934

LIBER 3 PAGE 247

RECORDED

HILLSDALE CO. MICH.

'98 AUG 7 AM 10 09

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT MEETING HELD ON 8-5-98 AL RINGENBERG, CO. REP.

HILLSDALE COUNTY REMONUMATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in

HILLSDALE COUNTY ADAMS TOWNSHIP

Located In: Corner Code

1. Public Land Survey T 6 S R 2 W H-3

2. Property Controlling in Section S T R

3. Miscellaneous S T R

Property in Sec. S T R

SURVEY & REMONUMENTATION

Register of Deeds Stamp & File Number

FEB 23 1999

SECTION

4. Lot No. , Recorded Plat 5. Private Claims

I, EDWARD W. REED, in a field survey on JULY 26, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. A dot is marked at the intersection of column H and row 3.

QUARTER CORNER COMMON TO SECTIONS 3 & 10

A. Description of original monument and accessories and/or subsequent restoration:

1973: A. JOHN HATT, SURVEYOR - SET SPIKE FROM SE. CORNER OF HOTEL BUILDING FROM WITNESS BY G. MARK, IN 1896 AND EAST FROM CENTERLINE OF R.R. TRACK FROM RAILROAD DRAWINGS,. RECORDED IN LCRC LIBER 1, PAGE 293

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SPIKE AS DESCRIBED BY HATT IN LIBER 1, PAGE 293

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: REPLACED SPIKE WITH 3/4" X 30 REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX SET FLUSH WITH PAVED ROAD SURFACE

- SE COR. OLD HOTEL BUILDING N 45 W 52.20'
NW COR. FURNITURE STORE S 60 E 91.18'
NW COR. NEW BANK BLD. N 55 E 67.65'
NE COR. STORE S 45 W 53.10'

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Edward W. Reed

Date August 7, 1998

EDWARD W. REED

Surveyor's Michigan License No. 33985

