



10491

RECORDED HILLSDALE CO. MICH.

18 OCT 15 PM 1 17

HILLSDALE COUNTY REMONUMENTATION CORNER LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REC. OF DEEDS

For corners in

HILLSDALE COUNTY ADAMS TWP. (County)

Located In: Corner Code #

- 1. Public Land Survey T 6S R 2 W H-7
2. Property Controlling in Section S T R SURVEY & REMONUMENTATION
3. Miscellaneous Property in Sec. S T R

FEB 23 1999

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat SECTION

5. Private Claims

Grid table with columns A-M and rows 1-13, containing numbers 1-36 and a dot at row 7, column H.

I, EDWARD W. REED, in a field survey on JULY 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

QUARTER CORNER COMMON TO SECTIONS 15 & 22

A. Description of original monument and accessories and/or subsequent restoration:

1825: GOVERNMENT SURVEY TO SET CORNER NO OTHER WITNESS TO CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON PIPE AS USED IN SURVEY BY S. MASON, SURVEYOR IRON PIPE IS ON LINE BETWEEN EAST & WEST CORNERS, AND 7.2 FEET EAST OF MIDWAY POINT

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON IN PLACE OF PIPE WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

- 18" TWIN WALNUT S 75 W 71.3'
12" CHERRY S 40 W 24.0'
PK NAIL IN 30" BOX ELDER S 30 E 27.48'
12" WALNUT N 30 E 70.3'
TEL PED S 63 E 53.9'
CAPPED IRON STAKE SOUTH 33.0'



AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]

Date 10-6-98

Surveyor's Michigan License No. 33985

EDWARD R. REED