

007942

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 255

HILLSDALE COUNTY REMONUMATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'98 AUG 7 AM 10 10

Judy VanZandt
REC. OF DEEDS



For corners in

HILLSDALE COUNTY
ADAMS TWP.

Located In:

Corner Code

- 1. Public Land Survey T 6 S R 2 W J-7
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____
- T _____ R _____
- 3. Miscellaneous S _____
- T _____ R _____
- Property in Sec. S _____
- T _____ R _____

Register of Deeds Stamp & File Number

**SURVEY &
REMONUMENTATION**

FEB 23 1999

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 26, 19 98
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

QUARTER CORNER COMMON TO SECTIONS 14 & 23

A. Description of original monument and accessories and/or subsequent restoration:
1872: GEO. MARKS, CO SURVEYOR, SURVEY # BK V, PAGE 59; STONE AND EARTHEN
1972: A. JOHN HATT, SURVEYOR; FOUND STONE AND EARTHEN, SET 3/4" IRON OVER STONE,
RECORDED IN LCRC # LIBER 1, PAGE 99


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE SET OVER STONE FROM WITNESS OF LIBER 1, PAGE 99

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE & PIPE, SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX, 4" BELOW GRAVEL ROAD SURFACE

- NAIL IN E SIDE OF 8" CHERRY, S 75 W 26.35'
- 12" DIA WOOD POST NORTH 26.6'
- NAIL N SIDE OF 8" CHERRY, S 70 E 64.25'
- POWER POLE, N 05 E 101.7'
- TEL. PED NORTH 29.2'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date AUGUST 5, 1998

Surveyor's Michigan License No. 33985