

007943

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 256

HILLSDALE COUNTY REMONUMATION CORNER
LAND CORNER RECORDATION CERTIFICATE '98 AUG 7 AM 10 10
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1970 AT MEETING HELD ON
AL RINGENBERG, CO. REP.

Judy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE COUNTY
ADAMS TWP.

Located In:

Corner Code #

1. Public Land Survey	T <u>6 S</u> R <u>2 W</u>	<u>K-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____	_____
	T _____ R _____	_____
3. Miscellaneous	S _____	_____
	T _____ R _____	_____
Property in Sec.	S _____	_____
	T _____ R _____	_____

Register of Deeds Stamp & File Number

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on JULY 26, 19 98
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

CORNER COMMON TO SECTIONS 13-14-23-24

A. Description of original monument and accessories and/or subsequent restoration:

1872: GEO MARK, CO. SURVEYOR; SURVEY BOOK V, PAGE 59. BRICK & STONE
1972: A. JOHN HATT, SURVEYOR; FOUND STONE AND BRICK, CHISELED "X" IN TOP OF STONE, SET IRON PIPE ON SIDE, RECORDED IN LCRC LIBER 1, PAGE 95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STONE WITH CHISELED "X" AND IRON AS DESCRIBED IN LIBER 1, PAGE 95

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REMOVED STONE, SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX IN PLACE OF STONE, 5" BELOW GRAVEL ROAD SURFACE.

NAIL IN N. SIDE OF 24" OAK,	S 80 W	105.9'
EAST END STEEL GATE POST,	N 48 W	77.8'
CENTER OF MULTIPLE CLUSTER BOX ELDER,	S 45 W	27.7'
CENTER OF TWIN CHOKE CHERRY,	S 60 E	81.6'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE CORNER

Signed by *Edward W. Reed*
EDWARD W. REED

Date AUGUST 5, 1998

Surveyor's Michigan License No. 33985