

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 346 OF 1990 AT A MEETING HELD ON _____
 AL. RINGENBERG, CO. REP.

034958

LIBER 5 PAGE 40

HILLSDALE COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
 HILLSDALE CO. MICH.
 03 OCT 11 AM 10:42

John J. Ringenberg
 REG. CLERK

For corners in

HILLSDALE Located In: Corner Code #
 (County)
 ADAMS TWP.

1. Public Land Survey T6S R2W I-11
 T R
 T R
 T R
2. Property Controlling S T R
 in Section S T R
3. Miscellaneous S T R
 Property in Sec. S T R

SURVEY &
 REMONUMENTATION

JAN 12 2001

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on Sept. 16 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Robert Clark, Jr., Apr. 1825: Set Post; Beech 6" N. 46° W. 19 lks.; Beech 6" N. 43° E. 26 lks.

Alan E. Ringenberg, LCRC L. 1, P. 544 #4817, Jul. 21, 1977: Measured existing fences in four directions and prorated existing lines of occupation with GLO Survey and reestablished corner. Set R.R. Spike; N. 40° W. 38.49' P.K. Nail E. side fence post; N. 25° E. 66.18' P.K. nail W. side 10" poplar; N. 60° E. 54.77' P.K. nail S.E. side Pwr. Pole.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. Spike and two of Ringenberg's references. 10" Poplar N. 25° E. 66.18' is gone. Fence post N. 40° W. 38.49' is tipped to West. Dug at position of R.R. spike. Nothing else found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. Spike with 3/4" x 30" iron with remonumentation cap in monument box and is accepted as the best available evidence of the position of the original corner.
 About in centerline N/S road & 3.5' S. of centerline E/W road.
 Found Nail S.W. side 18" Elm N. 55° W. 58.76'
 Top Cen. Tel. Stan. N. 30° W. 42.63'
 Found P.K. E. side R.R. tie post N. 30° W. 38.95'
 Top Cen. Tel Stan. S. 25° E. 54.68'
 Set Nail & Spotter Util. Pole N. 55° E. 55.00'

Signed by Frederick J. Cutcher Date _____
 Surveyor's Michigan License No. 24592

