

ACCEPTED BY THE HILLSDALE COUNTY SURVEY DEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1880, AT A MEETING HELD ON 10/21/00 AT AL RINGENBERG, CO. REP.

LIBER 5 PAGE 42

034960

RECORDED
HILLSDALE CO. MICH.
OCT 11 AM 10:42
John J. Cutchner
REG. DEEDS

**HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

HILLSDALE Located In: _____ Corner Code # _____
(County)

ADAMS TWP.

- 1. Public Land Survey T6S R2W K-11
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

**SURVEY &
REMONUMENTATION**
JAN 18 2001
SECTION
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Frederick J. Cutchner, in a field survey on Sept 18 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, Robert Clark, Jr., Apr. 1825: Set Post; Beech 11" N. 74° W. 19 lks.; Beech 6" S. 85° E. 10 lks.

A. John Hatt, LCRC L. 1, P. 339, #4071, Aug. 24, 1973; Set R.R. Spike; P.K. N. side 36" B. Oak S. 80° W. 122.95'; P.K. Nail N. side 30" Maple S. 78° E. 123.97' (see LCRC for additional information).

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. Spike 2" below pavement surface. Both references from LCRC remain. Dug at position of R.R. spike. Nothing else found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. Spike with 3/4" x 30" iron with remonumentation cap in monument box and is accepted as the best available evidence of the position of the original corner.
 About in centerline EW road and 4' W. of centerline N/S road.
 Top center tel. stan. N. 30° W. 37.60'
 Top center tel. stan. S. 30° W. 43.85'
 Set Nail & Spotter 14" Maple S. 53° E. 57.67'
 Set Nail & Spotter 14" Spruce S. 18° E. 100.13'



Signed by Frederick J. Cutchner Date _____
 Surveyor's Michigan License No. 24592