



LIBER 3 PAGE 125
REMONUMENTATION

118392

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'96 DEC 19 PM 2 20

Justy VanZandt
REG. OF DEEDS

For corners in

HILLSDALE

(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|----|---|----|------------|
| 1. Public Land Survey | T | 6S | R | 3W | A-11, B-11 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11	●											
12	31	32	33	34	35	36						
13												

I, JEFFREY BIESZK, in a field survey on 10 DECEMBER, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11:
1825 GLO
POST
15 B. OAK S37W 15 lks
11 HICKORY N37E 15 lks

B-11:
1825 GLO
POST
17 B. OAK S18W 37 lks
13 B. OAK N36E 38 lks

BURRIS
FOUND POINTED STONE
LCRC L1 P325
P. POLE N65E 67.34'
SIGN POST S60E 72.28'
SE COR MOBILE HOME N40W

GEORGE MARKS
SET STONE & EARTHEN
64.75'
10 HICKORY N81E 112.5 lks
6 SUG. S28W 84 lks

GEORGE MARK
STONE & EARTHEN
16 W. OAK N48.5E 37

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11: GEORGE MARK SET STONE AND EARTHEN BEING 20 LINKS NORTH OF M-11, T6S-R4W. I FOUND 3/4" PIPE ON NORTH EDGE OF ROAD EAST-WEST AND CENTERLINE ROAD NORTH AND SOUTH. DUG AND FOUND STONE. CORNER WAS 15 FEET NORTH OF INTERSECTION OF ROADS. ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

B-11: IN BURRIS LCRC HE SAID HE FOUND A POINTED STONE AND WITNESSED IT. I FOUND A 3/4" PIPE AT THE CORNER AS WITNESSED BY BURRIS BUT DID NOT FIND THE STONE. ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11:
SET 5/8" x 36" REBAR IN MON BOX
CENTER RISER N80W 35.22'
NAIL & TAG 10" CEDAR N40E 42.67'
NAIL & TAG 30" WALNUT S45E 57.95'
NAIL & TAG 42" MAPLE S25W 60.24'

B-11:
SET 5/8" x 36" REBAR
SE COR. MOBILE HOME N40W 64.55'
STOP SIGN POST S50E 20.38'
FENCE POST N85W 83.06'
POWER POLE N50E 66.90'

SURVEY &
REMONUMENTATION

MAY 16 1997

COMMISSION



Signed by *Jeffrey A. Bieszek*

Date 10 DECEMBER 1996

Surveyor's Michigan License No. PS#41093