



LIBER 3 PAGE 103  
HILLSDALE COUNTY  
REMONUMENTATION

107769  
RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 21 AM 11 14

For corners in

Hillsdale

Located In:

Corner Code -#

(County)

Fayette Twp.

- |                                       |                           |            |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey                 | T <u>6</u> S R <u>3</u> W | <u>C-4</u> |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
|                                       | T _____ R _____           | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____   | _____      |
|                                       | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                           |            |
| 5. Private Claims _____               |                           |            |

Judith Vomzandt  
REG. OF DEEDS

SURVEY &  
MONUMENTATION

JAN 30 1996

COMMISSION  
Register of Deeds Stamp & File Number

Frederick J. Cutcher, in a field survey on December 18, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Fayette Twp.

A. Description of original monument and accessories and/or subsequent restoration:  
Original Government Survey, April 28, 1825, Robert Clark Jr.: Hickory 7 in. S. 86° W. 34';  
B. Oak 15 in. N. 68° E. 28'.

John Maxson, no date: R.R. spike; N. 22° W., 53.46', P.K. 42" twin Oak; N. 57° E. 42.09' P.K. 6" Cherry; N. 88° E., 32.71', P.K. fnc. post; S. 77° W. 25.82' P.K. 14" Hickory.

Fred Cutcher, May, 1993: R.R. spike 2.5' W. of centerline Bunn Rd.; Nail S.E. side 18" twin Oak N. 18° W, 53.4'; P.K. Nail N.W. side cor. post N. 85° E., 32.7'; P.K. Nail P.P. S. 20° E. 79.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
Found R.R. spike 2.4'± W. of centerline N/S road.  
Found five of above references.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Replaced R.R. spike with 3/4"x36" iron rod with cap (County issue) in monument box and is accepted as the best available evidence of the position of the original corner.  
2.4'± W. of centerline of N/S road. 4'± S. of fence to East. 4'± N. of fence to West.  
P.K. 42" Tw. Oak N. 18° W., 53.50'.  
P.K. Fence Post N. 88° E., 32.71'.  
P.K. 14" Hickory S. 77° W., 25.82'.  
P.K. W. side P.P. S. 18° E., 79.3'.  
60D spike N. 85° E., 14.8'.

Signed by Frederick J. Cutcher  
Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

Date December 18, 1995