

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1970 AT A MEETING HELD ON 12/15/95 AT AL RINGENBERG, CO. REP.

LIBER 3 PAGE 87  
HILLSDALE COUNTY  
REMONUMENTATION

107573

RECORDED  
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 15 PM 1 03

For corners in

Hillsdale  
(County)  
Fayette Twp.

Located In: Corner Code #

1. Public Land Survey	T 6 S R 3 W	D-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Judy VanZandt*  
REG. OF DEEDS  
CONVEY &  
MONUMENTATION

JAN 30 1996

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Frederick J.  
Cutcher

in a field survey on November 12, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, April, 1825, Robert Clark Jr.: Set post; W. Oak 7 in.  
S. 62° E., 44; W. Oak 9 in. N. 54° W., 6.

Survey No. 793, March 16, 1876, George A. Mark: Stone 24", Hick. 10" S. 1° W., 33 lks.;  
Hick. 9" S. 49-1/4° W., 27 lks.

LCRC Liber 1, Page 604, August 6, 1979, Bruce A. Leone: Stone obliterated; set 4" diameter Harrison monument 6" below grade; P.K. E. side power pole #895 N. 1° W., 35.56';  
P.K. S.W. side 10" Elm S. 34° E., 62.83'; P.K. nail S.W. side service pole S. 52° E., 54.57'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison 5' N. of centerline of gravel road.

Two of above references were found.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5		●											
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Fayette Twp.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced Harrison monument with 3/4"x36" iron rod with cap (County issue) and is accepted as the best available evidence of the position of the original corner.

5' N. of centerline of gravel road.  
P.K. E. side power pole #895 N. 1° W., 35.56'.  
P.K. S.W. side service pole S. 52° E., 54.57'.  
N.W. cor. conc. blk. porch S. 10° W., 70.52'.  
N.E. cor. house #3531 S. 22° E., 78.44'.



Signed by *Frederick J. Cutcher*  
Frederick J. Cutcher  
Surveyor's Michigan License No. 24592

Date December 4, 1995