

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1970 AS A MEETING HELD ON 12/15/95 AT AL RINGENBERG, CO. REP.

LIBER 3 PAGE 91
HILLSDALE COUNTY
REMONUMENTATION

107577
RECORDED
HILLSDALE CO. MICH.
'95 DEC 15 PM 1 03

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code #
<u>Fayette Twp.</u>		
1. Public Land Survey	T <u>6</u> S R <u>3</u> W	<u>E-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Judy VanZandt
REG. OF DEEDS
SURVEY &
MONUMENTATION
JAN 30 1996
Register of Deeds Stamp & File Number
COMMISSION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J.

I, Cutcher, in a field survey on November 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
Original Government Survey, 1825, Robert Clark Jr.: W. Oak 7 in. N. 45 $\frac{1}{2}$ ° W., 2.38';
W. Oak 17 in. N. 51 $\frac{1}{2}$ ° E., 1.93.

LCRC Liber 1, Page 605, August 6, 1979, Bruce A. Leone: Fd. stone 3' below grade from Survey 1077 witnesses. Set 4" Harrison over stone 2" below grade: 48" Maple S. 14° W., 62'; i.p. (MSHD) N. 21° E., 11.98'; P.K. S.W. side 30" Wild Cherry N. 43° W., 31.77'; P.K. S.W. side 12" Walnut N. 8° W., 53.23'; P.K. S.E. side 24" Oak N. 40° E., 54.31'; P.K. S.W. side 15" Wild Cherry S. 61° E., 32.61'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found Harrison Monument over stone from remaining witnesses.
Four of above references were found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Replaced Harrison with 3/4"x36" iron rod with cap (County issue) and is accepted as a careful and faithful perpetuation of the position of the original corner. Reset Harrison on East side of remonumentation bar, 6" below surface.

4.7' South of fence line. 19' West of fence to North.
Face of 36" Oak N. 40° E., 53.1'.
Fd. Nail E. side R.R. tie North, 4.85'.
Fd. Nail S. side R.R. tie N. 70° E., 20.43'.
Fd. P.K. S.W. side 24" W. Cherry S. 61° E., 33.0'.
I.P. (MSHD) N. 21° E., 11.98'.

Signed by Frederick J. Cutcher Date December 4, 1995
Surveyor's Michigan License No. 24592