



107581

RECORDED

HILLSDALE CO. MICH.

'95 DEC 15 PM 1 04

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hillsdale

(County)

Fayette Twp.

Located In:

Corner Code =#

- 1. Public Land Survey T 6 S R 3 W F-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Julie VanZandt
REG. OF DEEDS

SURVEY &
MONUMENTATION

JAN 30 1996
Register of Deeds Stamp & File Number

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5			●										
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Fayette Twp.

Frederick J. Cutcher in a field survey on November 21, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, 1825, Robert Clark Jr.: Set post; W. Oak 9 in., N. 31° W., 27; B. Oak 14 in. S. 37° W., 56.

Todd Clow, Ringenberg Eng., April 28, 2978: 1/2" iron bar; 6' North of fence; Nail & washer E. side p.p. N. 30° W., 24.12'; P.K. E. side Cherry 10" S. 60° W., 50.78'; P.K. E. side 6" Cherry S. 20° E., 28.16'; (1985) P.K. W. side P.P. N. 10° E., 86.24'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2' iron rod 20' South of power line, 6' North of fence in old lane.

Four of above references were found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Angled 3/4"x36" iron rod with cap (County issue) over 1/2" iron rod found and is accepted as the best available evidence of the position of the original corner.

20' South of power line, 6' North of fence in old lane.

Nail & washer E. side P.P. N. 30° W., 24.12'.

P.K. E. side 10" Cherry S. 60° W., 50.78'.

P.K. E. side 6" Cherry S. 20° E., 28.16'.

P.K. W. side P.P. N. 10° E., 86.24'.

P.K. S. side P.P. N. 82° E., 106.0'.

Signed by *Frederick J. Cutcher*

Date December 5, 1995

Surveyor's Michigan License No. Frederick J. Cutcher 24592