



LIBER 3 PAGE 93
HILLSDALE COUNTY
REMONUMENTATION

107579

RECORDED
HILLSDALE CO. MICH.

'95 DEC 15 PM 1 03

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

SURVEY &
DOCUMENTATION

JAN 30 1996
Register of Deeds Stamp & File Number
COMMISSION

For corners in

Hillsdale
(County)
Fayette Twp.

Located In:

Corner Code #

- 1. Public Land Survey T 6 S R 3 W G-3
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Frederick J. Cutcher

I, Frederick J. Cutcher, in a field survey on November 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Fayette Twp.

A. Description of original monument and accessories and/or subsequent restoration:

Corner common to Sections 3, 4, 9 & 10, Town 6 South, Range 3 West.

Original Government Survey, 1825, Robert Clark, Jr.: W. Oak 20 in., N. 35° W., 19½'; B. Oak 11 in. N. 83° E., 29½'.

Survey No. 1095, June 4, 1889, R.J. Coryell: Est. iron; Hick. 12" N. 86° E.

LCRC Liber 1, Page 411, June 19, 1974, A.J. Hatt: Fd. 1" iron pipe as used for cor. by Maumee Sites Sub. (L7/P5 Plats); Nail S. side 12" Cherry E., 33.15'; Nail W. side 12" Cherry N., 12.08'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe in the intersection of the remains of fence/stone row.

Found stump of one of above references.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4"x36" iron rod with cap (County issue) inside iron pipe found and is accepted as the best available evidence of the position of the original corner. Set steel fence post on South side.

In line with tree row to North.
Nail N. side 12" Hickory S. 60° W., 13.0'.
P.K. W. side R.R. tie cor. post S. 37° E., 52.24'.
Nail W. side 12" Hickory South, 12.35'.
Nail E. side 8" Hickory North, 26.63'.

Signed by Frederick J. Cutcher

Date December 5, 1995

Surveyor's Michigan License No. Frederick J. Cutcher 24592