

**SURVEY &
REMONUMENTATION**

1993

COMMISSION

REMONUMENTATION

88324

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 22

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

'93 DEC 22 PM 2 20

For corners in
Hillsdale

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>6S.</u> R <u>3W.</u> | <u>G-8</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | § _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Judith VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Frederick J. Cutcher

I, Frederick J. Cutcher, in a field survey on December 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M.S.H.D. in survey CS #30032A by Max Walter, Survey Chief reported: "Found stone in road and raised with 1" pipe to blacktop surface, approx. 3' N. of centerline of blacktop surface".

LCR Liber 1, Page 135, Jun. 9, 1972 by A. John Hatt: Found pipe 1" below surface. Set R.R. Spike at blacktop surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found R.R. spike over 1" pipe over stone.
This corner has been used on many surveys in this area.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced R.R. Spike over 1" pipe over stone with 3/4" x 36" steel rod with cap (County issue) in monument box. 3.5'± North of centerline of Mechanic Street.
Top of fire hydrant N 42° W 41.55'
P.K. Nail in W. side of Pwr. pole N 55° E 44.80'
Center of water valve N 15° E 21.85'
P.K. Nail in S.W. side of guy pole N 30° W 33.82'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592

Date December 22, 1993