

1993

LIBEER 3 PAGE 14

OCCUPATION

RECORDED 88316 HILLSDALE CO. MICH.

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'93 DEC 22 PM 2 19

Judy VanZandt REG. OF DEEDS

For corners in

Table with columns: Located In, Corner Code. Rows for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, John E. Maxson in a field survey on 22 December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- G-13
GLO, 1823, 11 Beech, N50W, 6 lks
6 Beech, N58E, 15 lks
Co Sur 1871, Stone
Stone iron, N45W, 70.5 lks
14 Butternut, S20E 106 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13
Found Iron and Accepted as the best available evidence of the position of the original Corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13
Reset 5/8 x 36 rebar w/cap in mon. box
N41E 50.92' 34" Maple
S35E 40.94' 30" Maple
S75W 113.04' 40" Maple
N14W 109.01' P. Pole
N73E 26.94' 30" Maple
East 53.46' 1/2" rebar



Signed by [Signature]

Date 22 December, 1993

Surveyor's Michigan License No. 27454