

HILLSDALE COUNTY
REMONUMENTATION

RECORDED
HILLSDALE CO. MICH.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'95 DEC 15 PM 1 04



For corners in:

Hillsdale
(County)

Located In:

Corner Code #

Fayette Twp.

T 6 S R 3 W

I-4

1. Public Land Survey

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Judy VanZandt
REG. OF DEEDS

SURVEY &
MONUMENTATION

JAN 30 1996
Register of Deeds Stamp & File Number

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Fayette Twp.

Frederick J.
Cutcher

November 14, 1995

I do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original Government Survey, 1825, Robert Clark, Jr.: Set post; B. Oak 6 in. East 80; W. Oak 15 in. N. 12° E., 28.

Survey 1056, March 27, 1888, George A. Mark: Stone & brick (no witnesses).

LCRC Liber 1, Page 413, June 19, 1974, A. John Hatt: Fd. 3/4" iron pipe 6" below surface of road; P.K. S.E. side P.P. N. 80° E., 80.40'; P.K. S.E. side 26" Ash N. 30° E., 31.02'; in line with fence to North.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron bar as called for 15" below road surface (road reworked summer 1995 and filled.)

In line with fence to North.

None of above references were found.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed 3/4"x36" iron rod with cap (County issue) angled over iron bar and is accepted as the best available evidence of the position of the original corner.

In line with fence row to North, in centerline E/W road, 4'± W. centerline of road South.

Top cen. tel. stan. North 19.53'.
Nail S.E. side P.P. N. 50° E., 33.66'.
Nail S. side 36" Hickory N. 78° E., 88.80'.
Cen. 6" Maple N. 48° W., 66.8'.
N.W. end of CMP S. 60° E., 69.50'.

Signed by Frederick J. Cutcher
Frederick J. Cutcher

Date December 5, 1995

Surveyor's Michigan License No. 24592