

1993

LIBER 3 PAGE 13

COMMISSION

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED 88315
HILLDALE CO. MICH.

'93 DEC 22 PM 2 19

Judy VanZandt
REG. OF DEEDS

For corners in

	Located In:	Corner Code #/
<u>HILLDALE</u>		
1. Public Land Survey	T <u>6S</u> R <u>3W</u>	<u>I-11, I-12, I-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John E. Maxson in a field survey on 22-December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-11 GLO, 1823, 30 Oak, N32W, 27 lks 10 Oak, N80W, 26 lks LCRC, 1981, Ringenberg L2, P42 Iron in Mon. Box	I-12 GLO, 1823, 17 Oak, South 7.5 5 Ironwood, N60W, 17 lks LCRC, 1981, Ringenberg, L2, P42 RR Spike	I-13 GLO, 1823, 10 Beech, N57W, 19 lks 9 Beech, N53E, 47 lks LCRC, 1992, Ringenberg, L648, P106 Iron Bar
--	--	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-11 Found iron from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner	I-12 Found RR Spike from Ringenberg LCRC and accepted as the best available evidence of the position of the original Corner	I-13 Found Iron Bar and one witness from Ringenberg LCRC and accepted as the best available evidence of the original Corner
---	---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-11 reset 5/8 x 36 rebar with cap in mon. box N40E 41.90' THydrant S22E 48.84' 14"Maple S54E 37.27' State Hwy BM N47E 32.89' State Hwy ref pt S60W 43.08' State Hwy ref pt	I-12 reset 5/8 x 36 rebar with cap in mon. box N45E 39.82' 18"Hickory S53E 64.12' NW Cor Hse#151 N15W 95.13' 18"Hickory S61W 59.28' 18"Maple	I-13 reset 5/8 x 36 rebar with cap in mon. box S35W 30.38' 36"Maple East 11.99' P.Pole N30W 30.65' 10"Maple N07E 31.76' SE Cor Brk Pillar
--	--	---

Signed by *John E. Maxson* Date 22 December, 1993
Surveyor's Michigan License No. 27454

