

**SURVEY &
REMONUMENTATION**

1993

LIBER 3 PAGE 19

COMMISSION REMONUMENTATION 88321
LAND CORNER RECORDATION CERTIFICATE

RECORDED
HILLSDALE CO. MICH.

Filing Requirement of Act 74, Mich. P.A. 1970 '93 DEC 22 PM 2 20

For corners in
Hillsdale

(County)	Located In:	Corner Code #
1. Public Land Survey	T 6S. R 3 W.	K-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Judy VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Frederick J. Cutcher, in a field survey on December 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by George Mark dated March 23, 1880 in Book 6, entry 848: Stake, stone & brick.
LCR by Robert E. Burris, Sr. dated October 12, 1973: set 3/4" x 30" iron pipe.
This corner recorded in Liber 1, Page 357 LCR.
Burris set this corner by proportional measurements between fences using deed distances.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found a 1/2" x 18" iron rod in centerline of E/W road & 4'± E. of centerline N/S road.

Three references to this corner remain and this corner has been used over past years and recently by area surveyors.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1/2" x 18" iron with 3/4" steel rod with cap (County issue). (3/4" x 36" steel rod)
In centerline of E/W road & 4'± E. of centerline of N/S road.
Nail in 4" Hickory N 55° E 58.65'
Nail in N.E. side of Telephone pole N 43° W 60.31'
P.K. Nail in N.E. side of Pwr. pole S 40° W 89.02'
P.K. Nail in N. side of Pwr. pole N 76° W 153.2'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher Date December 21, 1993
Surveyor's Michigan License No. 24592