

1993

88320

RECORDED
HILLSDALE CO. MICH.

'93 DEC 22 PM 2 20

LIBER 3 PAGE 18

COMMISSION REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970.

For corners in
Hillsdale
(County)

Located In: Corner Code #

1. Public Land Survey	T <u>6S.</u> R <u>3W.</u>	<u>K-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Judy VanZandt
REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Frederick J. Cutcher

I, Frederick J. Cutcher, in a field survey on December 21, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Survey by George A. Mark dated March 23, 1880, Book 6 Ref. No. 848: Stake & Stone. W. Oak 18 S 45° E 51 1/4 links; Hickory 8 N 66° E 57 1/4 links.

LCR dated October 10, 1974 by Robert E. Burris, Sr.: Found iron pipe. This is recorded in Liber 1, Page 425 of LCR.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On this date I found an iron pipe. One reference remains: S 40° E 29.58' P.K. Nail in S.W. side 16" Oak.

Dug down approximately 24" but did not find stone.

This corner has been used on numerous surveys in this area.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

Replaced iron pipe with 3/4" x 36" steel rod with cap (County issue).
P.K. Nail in 16" Oak S 40° E 29.58'
Nail in N.W. side Pwr. pole N 78° E 18.98'
Top center of Telephone stanchion N 70° E. 16.12'
P.K. Nail in N. side of Pwr. pole S 85° W 138.75'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by Frederick J. Cutcher Date December 21, 1993
Surveyor's Michigan License No. 24592