

127893

RECORDED
HILLSDALE CO. MICH.

'97 NOV 3 PM 4 19

Judith Wornjardt
REG. OF DEEDS

**SURVEY &
REMONUMENTATION**
FEB 11 1998
SECTION

Register of Deeds Stamp & File Number

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 348
OF 1992 AFTER A MEETING HELD ON
Edward W. Reed
AL RINGENBERG CO. REP.

LIBER 3 PAGE 205

**HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>HILLSDALE</u>	Located In:	Corner
Code #		
(County)		
ALLEN TWP.		
1. Public Land Survey	T <u>6</u> S R <u>4</u> W	<u>A-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, EDWARD W. REED, in a field survey on MAY 5, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

SOUTHWEST CORNER SECTION 30, NORTHEAST CORNER SECTION 31

NO INFORMATION AVAILABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

AT DEPTH OF 38" FOUND OLD IRON FRAGMENTS AROUND POINTED STONE
FITS GLO OFFSET OF 56 LINKS

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX FLUSH WITH ROAD PAVEMENT

TEL PED., N75W 41.5'
SE CORNER HOUSE, N44W 106.4'
10" MAPLE, N34W 40.1'
TEL PED, N70E 53.3'
48" TRIPLE ASH, N56E 64.3'
BRANCH COUNTY CORNER, NORTH 36.96'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed* Date MAY 7, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985