

022237

RECORDED
HILLSDALE CO. MICH.

99 SEP -2 AM 9:16

Judy VanZandt
REG. OF DEEDS

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE CORNER UNDER MICHIGAN PUBLIC ACT 74 OF 1970 MEETING FIELD OF 1999
Alan E. Ring
ALAN E. RING

LIBER 3 PAGE 322

**HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>HILLSDALE</u> (County) ALLEN TWP.	Located In:	Corner Code #
1. Public Land Survey	T6S R4 W	C-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on July 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O., 12/14/1825, Wm. Brookfield: Intersected North boundary 103 lks. West of Post, set post: Birch 24" S. 49° E. 43; Birch 14" S. 9° W. 57.

Survey No. 755, 11/8/1876, Geo. A. Mark: Stone 20". Earthen, brick & stones (no witnesses).

LCRC No. 2686, L. 1, P. 123, 6/6/1972, A.J. Hatt: Found iron pipe in pavement; fence line running North is East 67.98°; S.E. corner square concrete post N. 55° W. 68.0°; Nail E. side 12" cedar S. 5° E. 38.1'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 18" iron rod in centerline Jonesville Road, 67.57' West of C-13, Litchfield Township.

Three references remained from LCRC.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" diameter iron with County Remonumentation Cap in monument box and is accepted as the best available evidence of the position of the original corner. (Replaced 5/8"x18" iron rod).

In centerline Jonesville Road, 67.57' West of C-13, Litchfield Township; nail & spotter 20" Walnut S. 36° W. 43.00°; nail & spotter 18" Cedar S. 6° E. 38.65°; nail & spotter 18" Box Elder North 46.94°; nail & spotter fence corner post N. 68° E. 82.86'.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5		4		3		2		1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. 24592



Date 7/30/99