



HILLSDALE COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE '98 AUG 5 AM 10 25 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Hillsdale (County)	Located In:	Corner Code #
1. Public Land Survey	T6S R4W	C-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Judy VanZandt REG. OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Frederick J. Cutcher, in a field survey on May 16, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G. L. O. by Wm. Brookfield, 1825: Red Oak 18" S. 22° E. 59 lks; White Oak 18" N. 63° W. 57 lks.

LCRC 2682, A. John Hatt, 5/31/72: Found "T" iron set by H.W. Dorsey, May 1969 in C.P. Survey file 3386: 24" Walnut W.N.W.23.97'; 12" Oak, S.E. 76.17'.

Ringenberg Records, 4/10/78: 1/2" iron bar set over "T" bar: P.K. S. side 24" Walnut S. 80° W. 23.75'; P.K. S. side fence post S. 70° W. 30.41'; P.K. W. side 12" Oak S. 30° E. 76.43'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4/17/98 Found 1/2" iron rod bent, about 3.5' E. of centerline Hog Creek. Found bent and twisted iron bar on East side of iron rod.  
5/16/98 Dug down 18", found stones.

Three witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" county remonumentation bar with cap in monument box and is accepted as the best available evidence of the position of the original corner.

About 3' East of centerline of Hog Creek Road, in line with fence to East and about 8' North of fence to West.

Nail & Spotter South side 24" Cherry N. 39° E. 62.8'

Center fence post S. 86° E. 28.65'

Nail & spotter East side 36" Oak S. 23° E. 76.7'

P.K. Nail in fence corner post S. 79° W. 30.36'

Nail & spotter in North Side 36" Walnut West 44.23'.

Signed by Frederick J. Cutcher

Date AUG. 5, 1998

Surveyor's Michigan License No. 24592

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

