

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1980 AT MEETING HELD ON _____ AL RINGENBERG, CO. REF

HILLSDALE COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

98 AUG 5 AM 10 25
Judy VanZandt
REG. OF DEEDS

For corners in

Hillsdale (County) Located In: Corner Code #
1. Public Land Survey T6 S R4 W C-9
T R
T R
T R
2. Property Controlling in Section S T R
S T R
3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on July 25, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		●										
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Common corner Sections 19, 20, 29 & 30

G.L.O. by Wm. Brookfield, 1825: R. Oak 20" S. 79° E. 23 lks; W. Oak 10" N. 22° E. 50 lks.

Survey No. 749, Geo. A. Mark, 6/20/1876: Stone 36" Earthen & Brick: Sugar 10" N. 45°2' E. 54 1/4 lks.

Survey No. 836, George A. Mark, 7/30/1879: Stone 36" Earthen & Brick: Sugar 12" N. 45°2' E. 54 1/4 lks.

A.J. Hatt, 8./28/58: Found large stone & brick from witnesses of 1876 survey: Nail in 20" Maple N. 85° W. 24.4'; Nail in tree N. 20° W. 69.8'; Nail in 20" Maple N. 45° E. 36.8'; conc. cor. post S. 40° E. 40.0'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Dug from A.J. Hatt references in intersection of Darling Road and Hog Creek Road. Found large stone surrounded by broken brick & crockery, 2" below gravel road surface. Stone appears to be tipped to the South. References found fall on North side of stone.

Four witnesses were remaining.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 36" county remonumentation iron on North side of stone to fit references as best as possible and is accepted as the best available evidence of the position of the original corner. Unable to set monument box, due to position of stone. Remon iron is angled with top at correct position.

N.W. face at bottom concrete post S. 35° E. 39.30'
Found nail N. side 24" Maple N. 49° E. 36.27'
Nail & spotter N.E. side 36" Maple N. 23° W. 69.85'
Nail & spotter N. side 36" Maple N. 82° W. 25.35'
Nail & spotter N.W. side 36" Maple S. 60° W. 28.97'

Signed by Frederick J. Cutcher

Date AUG. 5, 1998

Surveyor's Michigan License No. 24592

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION