

RECORDED
 HILLSDALE CO. MICH.
 022243
 99 SEP -2 AM 9:16
Julie VanJanak
 REG. OF DEEDS

LIBER 3 PAGE 328

HILLSDALE COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE Located In: Corner Code #
 (County)
 ALLEN TWP.

- 1. Public Land Survey T ___ R ___
- T ___ R ___
- T ___ R ___
- T ___ R ___
- 2. Property Controlling S 4 T 6S R4W F-1
- in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
- Property in Sec. S ___ T ___ R ___

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on July 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O.: No information, this North 1/4 Post was not set in original G.L.O.

Survey No. 1234, 6/1899, Geo. A. Mark: Stone 18", plow point & bottle; B. Walnut 4" S. 52-1/4° E. 90-1/2 lks.

Survey Notes, 8/21/1989, Ringenberg Eng.: No indication of what was found; S.E. corner barn foundation N. 60° W. 127.9'; P.K. N. side 20" Maple S. 80° W. 141.4'; P.K. N. side 12" Locust S 70° E. 233.9'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" diameter iron 1' North of centerline Jonesville Road, 36.30' West of F-13 Litchfield Township.

Two of Ringenberg's witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron found with 3/4" diameter iron with County Remonumentation Cap in monument box. This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

1' North of Jonesville Road, 36.20' West of F-13, Litchfield Twp.; nail & spotter 15" Maple S. 80° W. 141.60'; nail & spotter 12" Walnut N. 78° W. 185.57'; iron w/cap South 33.00'; iron w/cap N. 48° E. 34.45'.

Signed by Frederick J. Cutcher
 Surveyor's Michigan License No. 24592



Date 7/30/99