

127896

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 208

'97 NOV 3 PM 4 19

HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 11 1998

SECTION
Register of Deeds Stamp & File Number

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY FEES GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 346
OF 1980 AT A MEETING HELD ON
Al Ringenberg
AL RINGENBERG, CO. REC.

For corners in

| | | |
|-------------------------|---------------------------|------------|
| HILLSDALE | Located In: | Corner |
| Code # | | |
| (County) | | |
| ALLEN TWP. | | |
| 1. Public Land Survey | T <u>6 S</u> R <u>4 W</u> | <u>G-7</u> |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| | T ___ R ___ | _____ |
| 2. Property Controlling | S ___ T ___ R ___ | _____ |
| in Section | S ___ T ___ R ___ | _____ |
| 3. Miscellaneous | S ___ T ___ R ___ | _____ |
| Property in Sec. | S ___ T ___ R ___ | _____ |

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 15-16-21-22


NO INFORMATION AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND LARGE POINTED STONE WITH BROWN PIECES OF BROWN CLAY TILE ON TWO SIDES IN LINE WITH FENCES RUNNING EAST & WEST
SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD SURFACE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

NAIL & WASHER N. SIDE 30" OAK, S85W 38.00'
NAIL & WASHER W. SIDE POWER POLE, S15E 83.71'
SW CORNER RAILROAD TIE ANCHOR POST, WEST 26.35'
CORNER TEL PED. N10W 147.00'
IN LINE WITH FENCES RUNNING EAST & WEST
C/L OF N-S ROAD, EAST 4.0'



AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed* Date OCTOBER 14, 1997

EDWARD W. REED
Surveyor's Michigan License No. 33985