

127895

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 207

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
10/14/97
AL RINGENBERG CO. REP.

**HILLSDALE COUNTY REMONUMENTATION CORNER
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

'97 NOV 3 PM 4 19

Judy VanZandt
REC. OF DEEDS

For corners in

<u>HILLSDALE</u>	Located in:	Corner
Code #		
(County)		
ALLEN TWP.		
1. Public Land Survey	T <u>6</u> S R <u>4</u> W	<u>G-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling	S ___ T ___ R ___	_____
in Section	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

**SURVEY &
REMONUMENTATION**

FEB 11 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, EDWARD W. REED, in a field survey on OCTOBER 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
QUARTER CORNER COMMON TO SECTIONS 21 & 22

NO INFORMATION AVAILABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

DUG LARGE HOLE, FOUND NOTHING, PROBABLY REMOVED FOR CONSTRUCTION OF GAS LINE

RESET CORNER MIDWAY AND ON LINE BETWEEN CORNER NORTH & SOUTH
SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD GRADE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

GAS HEAD, S70E 20.3'
NE CORNER CONC. CULVERT, N50W 29.5'
NAIL & WASHER W. SIDE POWER POLE, S35E 51.55'
GAS HEAD RISER HEAD, N30E 36.0'
NAIL & WASHER S. SIDE 10" CHERRY, N76W 75.00'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER

Signed by *Edward W. Reed*

Date OCTOBER 14, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985

