

127897

RECORDED
HILLSDALE CO. MICH.

LIBER 3 PAGE 209

97 NOV 3 PM 4 19

**HILLSDALE COUNTY REMONUMENTATION CORNER,
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-14-97 AT AL RINGENBERG, CO. REP

Janey VanLandt
REC. OF DEEDS

For corners in

<u>HILLSDALE</u>	Located In:	Corner
Code #		
(County)		
ALLEN TWP.		
1. Public Land Survey	T <u>6</u> S R <u>4</u> W	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

**SURVEY &
REMONUMENTATION**

FEB 11 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

EDWARD W. REED, in a field survey on OCTOBER 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER COMMON TO SECTIONS 21-22-27-28

NO INFORMATION AVAILABLE SINCE GLO

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND LARGE (2.5' X 3') STONE WITH BROWN CLAY TILE ON TWO SIDES, IN LINE WITH FENCE RUNNING WEST
SET 3/4" X 30" REBAR IRON WITH REMON CAP IN CI-MONUMENT BOX 4" BELOW GRAVEL ROAD GRADE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
IN LINE WITH FENCE RUNNING WEST
NAIL & WASHER W. SIDE 60" OAK, N30E 78.47'
NAIL & WASHER W. SIDE 60" OAK, N45E 43.12'
NAIL & WASHER W. SIDE 10" OAK, S60E 55.55'
W. END ROAD CULVERT, S30W 28.85'

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER



Signed by *Edward W. Reed* Date OCTOBER 14, 1997

EDWARD W. REED

Surveyor's Michigan License No. 33985