



REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

98 DEC 4 AM 11 47

For corners in

<u>HILLSDALE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>1W</u>	<u>A-1</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Jeffrey VanZandt
REG. OF DEEDS
SURVEY & REMONUMENTATION
FEB 23 1999
SECTION
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszek, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--------------------------------------|
| GLO set by Joseph Wampler | LCRC (Bruce Leone L 610, P 784) |
| 12" Birch N 57 E 4.5 lks | Harrison Monument. |
| 14" Poplar S 19 E 35 lks | PK 8" Swamp Willow N 70 W 112.89 ft. |
| | PK 6" Apple N 87 E 133.29 ft. |
| County Surveyor (Geo. A Marks 1887 & 1905) | PK 24" Maple S 71 E 88.67 ft. |
| Found stake and stone | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison monument set by Bruce Leone, dug and did not find stone or stake as did Leone. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Stop Sign N 70 E 43.38 ft.
- Stop Sign S 50 W 46.44 ft.
- Nail and tag Corner Fence Post S 40 W 39.61 feet
- Nail and tag Fence Post S 30 W 48.65 ft.



Signed by [Signature]
Surveyor's Michigan License No. 41093

Date 4 December 1998