

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON _____ AL RINGENBERG, CO. REC.

LIBER 3 PAGE 286

12388

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION

'98 DEC 4 AM 11 47

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

<u>HILLSDALE</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>1W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- LCRC (Bruce Leone L 610, P 792)
- Harrison Monument.
- PK 6" Elm S 89 E 120.85 ft.
- PK Railroad Fence Post S 30 E 36.53 ft.
- PK Fence Post S 16 E 60.79 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison monument set by Bruce Leone, who re-established location by proportionate measurement and found 3" pointed cedar and a steel stake on north side of cedar stake, dug and found cedar post as found by Leone. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- PK 6" Elm S 89 E 120.85 ft.
- PK Railroad Fence Post S 30 E 36.53 ft.
- PK Fence Post S 16 E 60.79 ft.
- M-2 T7S-R2W South 184.75 ft.



Signed by *[Signature]*
Surveyor's Michigan License No. 41093

Date 4 Decem Ber 1998