

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1990, AT A MEETING HELD ON 10/19/98 AT 8 A MEETING HELD ON AL RINGENBERG, CO. REP.

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Jeffrey VanZandt*  
REG. OF DEEDS

For corners in

<u>HILLSDALE</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7S</u> R <u>1W</u>	<u>A-4</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

County Surveyor (Geo. A. Marks 1871)  
Stake & Tile  
12" Lym S 45.5 E 80 lks  
Stake & Tile East 50 lks

LCRC (Bruce Leone L 610, P 794)  
Harrison Monument.  
PK Power Pole S 56 W 30.19 ft.  
PK Power Pole N 09 W 125.37 ft.  
PK 10" Walnut S 72 E 55.54 ft.  
PK 30" Maple S 30 E 92.18 ft.  
M-4 T7S-R2W South 151.86 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison monument set by Bruce Leone, who found cedar stake inside vertical clay tile, dug and found cedar post as found by Leone. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box  
Nail & Tag Power Pole S 70 W 30.05 ft.  
Nail & Tag 12" Walnut S 80 E 55.50 ft.  
Nail & Tag 26" Maple S 40 E 91.07 ft.  
Riser N 75 W 27.02 ft.  
M-4 T7S-R2W South 151.86 ft.



Signed by \_\_\_\_\_  
Surveyor's Michigan License No. 41093

Date 4 December 1998