



LIBER 3 PAGE 289

12391

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 4 AM 11 47

For corners in

HILLSDALE (County) Located in: Corner Code #
1. Public Land Survey T 7S R 1W A-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Judy VanZandt REG. OF DEEDS SURVEY & REMONUMENTATION FEB 23 1999 SECTION Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Jeffrey A. Bieszk, in a field survey on 25 Nov 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (5, A) contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark Post LCRC (Bruce Leone L 610, P 795) Harrison Monument. PK Power Pole S 31 W 60.11 ft. County Surveyor (Geo. A. Marks 1871) Stake PK Power Pole N 11 W 101.11 ft. 16" W. Oak S 59.5 E 73.5 lks PK Chinese Elm N 37 E 99.44 ft.. PK 8" Ash N 70 E 85.41 ft.. M-5 T7S-R2W South 141.49 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Harrison monument set by Bruce Leone, who found 17" pointed stone said stone being 141.49 feet North of said M-5 T7S-R2W (recorded 142.56 feet), dug and found stone as found by Leone. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box Nail & Tag Power Pole S 31 W 60.03 ft. Nail & Tag Power Pole N 11 W 100.94 ft. Stop Sign N 55 E 52.65 ft. Northwest corner of North Phone Box S 35 E 68.08 ft. M-5 T7S-R2W South 141.49 ft.



Signed by [Signature] Surveyor's Michigan License No. 41093

Date 4 December 1998