SURVEY PEER GROUP AS THE OFFICIAL COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A BINGENBERG CO. REP.

5. Private Claims

LIBER 3 PAGE 292

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970


'98 DEC 4 AM 11 47

	1	mondy our Jough
Located In: Corner	Code#	hen of DEEDS
T <u>7S</u> R <u>1</u> W _ TR	A-8	SURVEY & REMONUMENTATION
TR STR		FEB 2 3 1999
S TR S TR		SECTION
<u> </u>		Register of Deeds Stamp & File Numbe
rded Plat	·	3000
	T_7S R 1W	T_7S R 1W A-8 T_ R T_ R T_ R S_ T_ R

conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 comers, all in the same town and range, may be recorded on this certificate.

Α.	Description of original monument and accessories and/or subsequent	restoration:
	Not set by GLO	



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set iron on line between M-8 T7S-R2W and M-7 T7S-R1W at proportionate distance from M-9 T7S-R1W and said M-7. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap Road Sign South 18.00 ft. Nail & Tag 14" Twin Oak S 12 W 18.61 ft. Nail & Tag 10" Oak N 85 E 41.06 ft. Nail & Tag 6x6 Wood Fence Post N 15 W 35.90 ft.

Signed by _

Surveyor's Michigan License No.

Date 4 December