

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 6-23-98 MEETING HELD ON AL RINGENBERG, CO. REP.

LIBER 3 PAGE 293

12395

RECORDED HILLSDALE CO. MICH.

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

'98 DEC 4 AM 11 47

For corners in

HILLSDALE

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-------------------------------------|------------|
| 1. Public Land Survey | T <u>7</u> S R <u>1</u> W | <u>A-9</u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| | T <u> </u> R <u> </u> | <u> </u> |
| 2. Property Controlling in Section | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| 3. Miscellaneous Property in Sec. | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |
| | S <u> </u> T <u> </u> R <u> </u> | <u> </u> |

Julie VanZandt
REG. OF DEEDS

SURVEY & REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszka, in a field survey on 25 Nov., 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|-----------------------------|---------------------------------|
| GLO | LCRC (Glenn Richard L 1, P 535) |
| Post | 1/2" Iron |
| 24" B. Oak S 56.5 W 200 lks | Tel. Pedestal N 50 E 47.96 ft. |
| 8" Ash S 82.5 E 138 lks | 26" Twin Oak S 60 E 93.39 ft. |
| | 22" Twin Oak S 25 E 101.86 ft. |
| | 20" Oak S 35 W 82.34 ft. |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron set by Glenn Richard, who found small spike covered with asphalt 112.15 feet North of P.K. found at Northeast Corner Section 25, T7S-R2W, replace spike with 1/2" iron bar. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set 5/8" x 36" iron w/cap in Monument Box
- Nail & Tag 20" Oak S 20 W 77.35 ft.
- North Post Road Sign West 17.35 ft.
- Phone Box N 45 E 48.81 ft.
- Stop Sign N 60 E 61.00 ft.



Signed by *[Signature]*
Surveyor's Michigan License No. 41093

Date 4 December 1998