

12402

RECORDED
HILLSDALE CO. MICH.

'98 DEC 4 AM 11 47

Jeffrey A. Bieszk
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

ACCEPTED BY THE HILLSDALE COUNTY
SURVEY PEER GROUP AS THE OFFICIAL
CORNER UNDER MICHIGAN PUBLIC ACT 345
OF 1990 AT A MEETING HELD ON
Al Ringenberg
AL RINGENBERG, CO. REP.

LIBER 3 PAGE 300

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

HILLSDALE

(County)

Located In:

Corner Code #

1. Public Land Survey

T 7S R 1W C-5

T _____ R _____

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO

Post

9" Beech S62W 9 lks

12" Beech N6E 21 lks

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" pipe dug and found nothing. This iron was used to re-establish B-5 as in LCRC Liber 1 Page 572 and used in re-establish C-6 as in LCRC Liber 1 Page 497. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box

Stop Sign S15E 53.97 ft.

Stop Sign N15W 49.69 ft.

Phone Riser N45E 45.70 ft.

Flag Pole N60E 87.00 ft.



Signed by _____

Surveyor's Michigan License No. 41093

Date 4 Decem Ber 1998