

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON _____ AL RINGENBERG, CO. REP.

LIBER 3 PAGE 302

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

12404

RECORDED
HILLSDALE CO. MICH.

'98 DEC 4 AM 11 48

For corners in

HILLSDALE Located In: Corner Code #
(County)

1. Public Land Survey T 7S R 1W C-7
T _____ R _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Julie VanZandt
REG. OF DEEDS

SURVEY &
REMONUMENTATION

FEB 23 1999

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Jeffrey A. Bieszk, in a field survey on 25 Nov, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO	LCRC L1 P602 Alan Ringenburg
Post	Found Bolt
20" Sugar N15W 59 lks	21.65 ft. North CL M-34
12" Beech S63E 49 lks	Bore Hole Top Headwall E 56.77 ft.
LCRC L1 P515 Russell Cole	Corner Post S50W 43.13 ft.
Found bolt	
Corner post SW 43.16 ft.	Stop Sign SE 29.74 ft.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Bolt as in both Cole and Ringenburg LCRC. Cole found bolt as shown on M-34 Highway plan being 21.65 feet North of centerline. Accepted as the best available evidence to the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 5/8" x 36" iron w/cap in Monument Box
Nail & Tag Fence Post S45W 43.18 ft.
Stop Sign S86W 57.31 ft.
West Leg Stop Sign S30E 39.17 ft.
East Leg Stop Sign N20W 69.63 ft.



Signed by *Jeffrey A. Bieszk*
Surveyor's Michigan License No. 41093

Date 4 December 1998