

RECORDED
HILLSDALE CO. MICH.

'94 NOV 28 AM 11 07

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CO. REP.

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in

Hillsdale
(County)

Located In:

Corner Code #

1. Public Land Survey

T 7S R 2W

B-3

SURVEY &
REMONUMENTATION

2. Property Controlling
in Section

S T R
S T R

APR 27 1995

3. Miscellaneous
Property in Sec.

S T R
S T R

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3		●											
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Frederick J.

I, Cutcher, in a field survey on October 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

R.E. Burriss, LCRC Liber 1, Page 385, Jan. 7, 1974: Found 1/2" iron bar.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8"x22" iron bar at road surface in centerline of road. Replaced iron bar with 3/4"x36" County remonumentation bar in a monument box. This corner has been used on numerous surveys and plats in this area and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monument box
In centerline of Road
Concrete monument West 32.95'
S.W. corner of barn East 98.23'
S.W. side 20" Hickory S. 43° E., 49.09'
Center of 4" White Pine S. 47° W., 53.80'



Signed by Frederick J. Cutcher

Date November 27, 1994

Surveyor's Michigan License No. 24592