

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1970 AT A MEETING HELD ON 11-10-94 AL RINGENBERG, CO. REP.

RECORDED HILLSDALE CO. MICH.

'94 NOV 28 AM 11 07

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in

Hillsdale Located In: Corner Code #
(County)

1. Public Land Survey T 7S R 2W C-1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

SURVEY & REMONUMENTATION

APR 27 1995

Register of Deeds Stamp & File Number

COMMISSION

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Frederick J. Cutcher, in a field survey on October 27, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Records of A.E. Ringenberg: M. Vernier, April 11, 1975: Set R.R. spike 60.60' East of S.W. corner, Sec. 32, T6S, R2W.

R.E. Burris, LCRC, Liber 1, Page 483, June 9, 1974: used this corner as a witness for the S.W. corner of Sec. 23, T6S, R2W.

GLO = 91 links East of C-13, T6S, R2W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike in centerline of East/West road in line with fence to South. Dug down 30", found nothing. Set 3/4"x36" County remonumentation bar in monument box. This corner has recently been used as evidenced by P.K. nails with ribbon in trees and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4"x36" County remonumentation bar in monument box
 In centerline of East/West road and in line with fence to South
 N.W. corner house foundation South 12° E., 75.15'
 Nail & spotter South side 18" Hickory, N. 84° E., 70.23'
 Nail & spotter West side 24" Maple S. 50° E., 46.25'
 Top center telephone stanchion South, 26.78'
 West 60.60' S.W. corner, Sec. 32, T6S, R2W



Signed by Frederick J. Cutcher Date November 27, 1994

Surveyor's Michigan License No. 24592