

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 10-94 AL RINGENBERG, CO. REP.

RECORDED HILLSDALE CO. MICH.

'94 NOV 28 AM 11 07

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REG. OF DEEDS

For corners in
Hillsdale
(County)

Located In: Corner Code #

- 1. Public Land Survey T 7S R 2W
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

D-3
**SURVEY &
REMONUMENTATION**
APR 27 1995
COMMISSION

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Frederick J.
Cutcher

I, _____, in a field survey on November 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3		●										
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Survey #685, Apr. 15, 1874, R. Bullard, County Surveyor: Found stone, brick and earthen. W. Oak stump 35 links North; Hickory 6" North 32½° East, 90 links.

A.E. Ringenberg: T. Clow, May 9, 1983: Found 1" bar. Set ½" rebar.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found ½"x18" iron rod over 1"x22" iron rod in centerline of road. Dug down 30", found nothing. Replaced iron rods with ¾"x36" County remonumentation bar in monument box and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

¾"x36" County remonumentation bar in monument box
In centerline of North/South road
N.E. corner lift station S. 50° W., 53.80'
Nail in South side 36" Oak N. 87° E., 71.54'
Nail in North side 12" Chinese Elm N. 44° W., 42.40'
Nail in South side 10" Hickory S. 60° E., 44.60'



Signed by *Frederick J. Cutcher*

Date November 27, 1994

Surveyor's Michigan License No. 24592