



97373

RECORDED HILLSDALE CO. MICH.

'94 NOV 28 AM 11 07

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt REG. OF DEEDS

For corners in Hillsdale (County) Located In: Corner Code # E-1 SURVEY & REMONUMENTATION APR 27 1995 COMMISSION

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13. A dot is marked in cell E-4.

Frederick J. Cutcher, in a field survey on November 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Survey #685, Apr. 15, 1874, R. Bullard, County Surveyor; Found stone, brick and glass. R. Cole, LCRC Liber 1, Page 529, Dec. 1, 1976: Found + chiselled in top of stone in East going fence. GLO = 135 links East of E-13, T6S, R2W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found E-13, T6S, R2W, and used as a reference check. Measured 89.10' East per LCRC Liber 1, Page 259. Measured from P.K. in power pole S.E. 54.5'. Dug for stone. Neighbor says that stone used to be sitting above ground, no stone found. Set 3/4"x36" County remonumentation bar from E-13, T6S, R2W and power pole witnesses and is accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 3/4"x36" County remonumentation bar West 89.10' to E-13, T6S, R2W Bottom N.W. corner concrete post East, 24.05' Found P.K. nail 6" up N.E. side power pole, S. 50° E., 54.50' Center 8" Maple, N. 45° E., 9.6' Center 10" Maple, N. 55° E., 13.95' Center 12" Pine, S. 25° E., 4.75'



Signed by Frederick J. Cutcher Date November 17, 1994 Surveyor's Michigan License No. 24592