

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980. MEETING HELD ON 10/10/97. AL RINGENBERG, CO. REP.

LIBER 3 PAGE 201
 HILLSDALE COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

127742

RECORDED
 HILLSDALE CO. MICH.

'97 OCT 30 AM 10 18

Julia VanZandt
 REGISTER OF DEEDS

SURVEY &
 REMONUMENTATION

FEB 11 1998

SECTION

Register of Deeds Stamp & File Number

For corners in

Hillsdale Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T ___ R ___ _____
 T ___ R ___ _____
 T ___ R ___ _____
 T ___ R ___ _____

2. Property Controlling S 6 T 7S R 3W _____ B-1 _____
 in Section S ___ T ___ R ___ _____

3. Miscellaneous S ___ T ___ R ___ _____
 Property in Sec. S ___ T ___ R ___ _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Frederick J. Cutcher in a field survey on 9/22, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not set during the Original Government Survey.

Survey No. 1257, George Mark, May 1902: Found N. 1/4 Post from W. Oak 12" S. 2° W. 19 1/2 lks.

Records of Ringenberg Engineering, 5/22/84: R.R. spike 48.79 feet (GLO=48.84) East of B-13, S. 1/4 Post, Section 31, T6S, R3W, Hillsdale Township, 4.5' N. of centerline road. No references were given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 9-22-97 I found a R.R. spike per above.

No witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced R.R. spike with County remonumentation bar and cap in a monument box. This position was not established by the original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- S.W. cor. house N. 58° E. 117.70'
- N.W. cor. house S. 58° E. 123.35'
- Cen. 8" Maple N. 20° E. 122.63'
- Nail & spotter W. side 8" Oak S. 10° W. 39.10'

Signed by Frederick J. Cutcher
 Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date 10/29/97

