

ACCEPTED BY THE HILLSDALE COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/30/97 AT HILLSDALE AL RINGENBERG, CO. REP.

127741

RECORDED HILLSDALE CO. MICH.

'97 OCT 30 AM 10 18

LIBER 3 PAGE 200
HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Judy VanZandt
REC. OF DEEDS

For corners in

Hillsdale Located In: Corner Code #
(County)

1. Public Land Survey T7S R 3W C-1
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

SURVEY & REMONUMENTATION

FEB 11 1998

Register of Deeds Stamp & File Number SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1			●										
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Frederick J. Cutcher, in a field survey on 9/22, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Original Government Survey by William Brookfield, 1825: W. Oak 13" S. 20° E. 15 links;
W. Oak 11" S. 53½° W. 27 links.

Records of Ringenberg Engineering, 6/5/72: Set R.R. spike 48.84 feet (GLO = 48.84)
East of S.E. Corner, Section 31, T6S, R3W, Hillsdale Township.

No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

On 9-22-97 I found a R.R. spike per above.

No witnesses were found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced R.R. spike with County remonumentation bar and cap in a monument box and is accepted as best available evidence of the position of the original corner.

In centerline Bankers Road.
Nail & spotter N.E. side util. pole N. 60° W. 45.30'
N.E. cor. church ramp S. 13° W. 31.70'
N.W. cor. church S. 54° W. 74.00'
Nail & spotter S. side power pole N. 72° E. 71.25'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 29, 1997

