

127740

RECORDED
HILLSDALE CO. MICH.

'97 OCT 30 AM 10 18

Judith VanZandt
REC. OF DEEDS

**SURVEY &
REMONUMENTATION**

FEB 11 1998

Register of Deeds Stamp & File Number



LIBER 3 PAGE 199
HILLSDALE COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Hillsdale</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>5</u> T <u>7S</u> R <u>3W</u>	<u>D-1</u>
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Frederick J. Cutcher, in a field survey on 9/25, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
This corner was not set during the Original Government Survey.
No information was available regarding this corner. No references given.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
On 9-25-97 I found nothing. Measured between corner C-1 and E-1 and set corner 1/2 way and on line between C-1 and E-1.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
I set a County remonumentation bar and cap in a monument box 1/2 way and on line with C-1 and E-1. This position was not established by the original government surveyors. This monument is accepted as the best available evidence of the position of the corner.
51.48' East of D-13, T6S, R3W
2' N. of centerline Bankers Road. In line with old anchor post to South.
Nail & spotter N.E. side util. pole N. 55° W. 42.28'
Nail & spotter S.W. side util. pole S. 60° E. 58.95'
Cen. 12" apple tree N. 13° E. 79.75'
Nail & spotter N.W. side util. pole S. 77° W. 112.00'

Signed by Frederick J. Cutcher
Surveyor's Michigan License No. Frederick J. Cutcher 24592

Date October 29, 1997
10/29/97

